



[Visit Suncam.com for more courses](http://www.suncam.com)

Continuing Education Course #458  
Cast, Lift, and Release: Tilt-Up Concrete Walls  
Part 1: Construction

1. (Blanks imply choosing the best answer.) Tilt-up walls are constructed by pouring a series of reinforced concrete panels on the \_\_\_\_ whose sides are formed with \_\_\_\_.
- a. slope, tin
  - b. bare dirt, scaffolding
  - c. ground, wood
2. Wall panels are often the \_\_\_\_\_ elements that form the building's perimeter.
- a. cold-weather insulation
  - b. load-bearing
  - c. solar-collecting
3. Reinforced concrete has 1) the concrete \_\_\_\_\_ strength to resist axial loads and to provide stiffness, and 2) the strength and ductility of steel reinforcing in \_\_\_\_\_ to resist bending moments and cracking.
- a. tensile, compression
  - b. compressive, tension
4. Tilt-up walls must adhere to the limitations set forth in \_\_\_\_ of ACI 318 (2014 versions and later).
- a. 11.8
  - b. 14.8
  - c. 7.2
5. One of the main references for tilt-up concrete design is "Design Guide for Tilt-Up Concrete Panels (\_\_\_\_),"
- a. ACI 350.1
  - b. ACI 551.2
  - c. ACI 221
6. Some of these advantages of tilt-up wall panels are:
- a. only wood and nails are required, panels can be carried by hand
  - b. elimination of vertical formwork compared to cast-in-place walls, fast construction time
  - c. tall scaffolding required, minimal ground space required to cast panels
7. The construction of the panels for a 100,000 sf one-story building can take place in \_\_\_\_ days or less
- a. 2
  - b. 3
  - c. 30
8. For buildings using tilt-up panels, these are often \_\_\_\_\_.
- a. Gleaming, 40-story residential towers
  - b. one-story warehouses or one- to two-story office buildings

- c. parking ramps with continuous openings between floors and a proliferation of spandrel panels that hang from columns
9. Tilt-up concrete involves the use of a crane, which needs \_\_\_\_\_ space to maneuver
- a. minimal
- b. considerable
10. For seismic force resisting systems in building, the code puts limits on the \_\_\_\_\_ of precast shear wall systems, which applies to tilt-up concrete shear walls that fit under the broader definition of precast.
- a. height
- b. weight
- c. length
11. A \_\_\_\_\_ season may inhibit plans to pour panels, causing costs or delays.
- a. mild
- b. sunny
- c. rainy
12. Challenges arise if a building has interior or exterior \_\_\_\_\_ that need to be constructed.
- a. trellises
- b. pools
- c. curbs
13. If wall area exceeds \_\_\_\_\_ of the slab area available, the more likely casting beds will be required, or that stacking panels on site will be necessary. (Choose the best answer):
- a. 20%
- b. 50%
- c. 80%
14. Wall panel thickness typically varies from \_\_\_\_\_ to \_\_\_\_\_ inches:
- a. 5.5 to 10
- b. 1.5 to 3
- c. 12 to 16
15. When using a non-composite sandwich panel with insulation and an outside fascia layer, other than self-weight of the fascia, all loads should be resisted by the \_\_\_\_\_.
- a. fascia
- b. structural wythe
16. Panel finishes include \_\_\_\_\_ panel surfaces.
- a. smooth or rough
- b. only smooth
- c. only rough
17. Panels are always placed \_\_\_\_\_ so they can be leveled.
- a. totally flat against the foundations, forming a perfect fit
- b. on shims
18. Embed plates use \_\_\_\_\_ or \_\_\_\_\_ to help transfer load into the concrete wall.
- a. glue, wooden dowels
- b. welded headed studs, welded rebar
19. Air holes 3/4" in diameter should be used to allow air to exit from under the plate during \_\_\_\_\_.

- a. snow storms
  - b. strong wind events
  - c. consolidation of the concrete with a vibrator
20. \_\_\_\_\_ is added to increase strength and stability at wall panel opening jambs.
- a. Reinforcing
  - b. Leave-in -place wood formwork
21. If the axial load at the jamb is sufficiently large, \_\_\_\_\_ are required.
- a. panel air voids
  - b. ties
22. If the building slab isn't used to pour panels on, temporary slabs known as \_\_\_\_\_ slabs may be used.
- a. two-way
  - b. casting
  - c. continuously reinforced
23. General panel construction sequenced: 1) \_\_\_\_\_, 2) \_\_\_\_\_, 3) \_\_\_\_\_.
- a. 1) Casting slabs, 2) Panel formwork and pouring, 3) erecting and bracing panels.
  - b. 1) Erecting panels, 2) Casting slabs, 3) Panel formwork.
24. When building slabs are used to pour panels and drive cranes on, be aware of the possibility of \_\_\_\_\_, no matter the amount of planning.
- a. slab damage
  - b. bumpy slabs
25. With dropped footings, a(n) \_\_\_\_\_, may be required for the outer ring of slab.
- a. inflatable mattress
  - b. pour strip
26. To allow the formwork to pull away from the wall panels and to ensure the panels will easily lift off of the slab, \_\_\_\_\_ are used.
- a. form release agents
  - b. glues
27. The lifting cables of the crane are attached to cast-in inserts that are normally in the upward facing face of the panel, called a \_\_\_\_\_.
- a. facial
  - b. face lift
  - c. Botox treatment
28. Once panels are stood up straight, \_\_\_\_\_ can be attached.
- a. cameras
  - b. braces
29. The fewer the number of panels, the \_\_\_\_\_ the erection time.
- a. greater
  - b. lesser
30. Practical limits for panel weights are in the range of \_\_\_\_\_.
- a. 80,000#
  - b. 5,000#
  - c. 300,000#

[Purchase this course on Suncam.com](http://Suncam.com)